



Test Certification

14812 Hunter Lane
Midway City CA 92655
Phone: 714 450-5929 Fax: 714 829-3103

Serial Number	20030282-6
Test Date	6/15/2020
Record No	1618
P.O. Number	DONNA ANDERSON
Work Order No.	879

Page 1 of 1

Bill to Customer SE-0070692

Site Customer SE-0059993

Inframark Water Infrastructure Operation
1600 Avalon Parkway
Perris CA 92571

Inframark Water Infrastructure Operations (well #
1600 Avalon Parkway
Perris CA 92571

Flow Meter Totalizer Reading - Gallons

Site Location

Before Test Flow Meter 234908 x 1000

Prover No

well # 2

After Test Flow Meter 234910 x 1000

PT-001

Meter Manufacture Size and Model

Service Type

Test Cycle

Pipe Diameter

Pipe Area

Water Specialties, 6" MW506 Propeller W Flow

Test Only

6

28 2744

Technician

Manny



Customer Meter
Average Accuracy

97.50%

Pitot Tube Test Data

Customer Meter

Test No.	Pitot Tube Reading	Actual GPM	Totalizer (start)	Totalizer (end)	Net Volume	Net Volume (gallons)	Test Time (mm:ss:hss)	Measured GPM	Accuracy
1	1.9	53.721	234908	234909	1000	1000.00000	19:05:025	52.39	97.53%
2	1.9	53.721	234909	234910	1000	1000.00000	19:06:000	52.36	97.46%

Additional Information

Test only.
No repair or calibration performed.

Approved By: